



All Block Check-Off

Caleb Hubbell


Block Diagram



Functional Overview - Motor



Interface Verification for System Integration - Motor



Interface	Properties
robot_outside_envin	<ul style="list-style-type: none">• Surfaces include: tile, short carpet, concrete• Obstacles include: walls, chair legs, cords, clothing
robot_outside_motion	<ul style="list-style-type: none">• Speed on all surfaces must be greater than 0.3 m/s• Max speed > 0.3 m/s• 10 min or greater time in motion
capacity/reg_motors_dcpwr	<ul style="list-style-type: none">• 3-12 V DC• 0 - 0.7 A• 10% tolerance on input parameters
motors_movement/sensing_dsig	<ul style="list-style-type: none">• PWM DC signal powering 2 motors• PWM frequency of 1.6KHz.• Draw of 0 - 0.45A• Duty cycle of 0-40%• 2 active high inputs; 5V high, 0V low

Testing Plan Overview - Motor



2 Steps:

- A. Top Speed No Load Test
- B. Top Speed Max Current Draw Test

Conclusion:

If the block passes all of the listed tests, all interface properties have been verified and the block is ready for inclusion into the system.

Schematic and Testing Setup - Motor



Test Videos - Motor



Test A: Top Speed No Load Test



Test B: Top Speed Max Current Draw Test

Test Results - Motor

Numerical Results:

A. $V = 3.53V$. $I = 0.1A$. $R = 35.5\Omega$. $RPM = 150$.

Linear Velocity = $0.93m/s$


B. $V = 3.35V$. $I = 0.5A$. $R = 6.7\Omega$. $RPM = 54$.

Linear Velocity = $0.33m/s$


Results: Passed

Both linear velocities were above the required minimum velocity of $0.3m/s$. This demonstrates that the motor block is ready to be incorporated into the system for further testing and should not result in system damage or malfunctions.

Functional Overview - Movement Sensing / Motor Comm



Interface Verification for System Integration - Movement Sensing / Motor Comm



Interface	Properties
robot_outside_envin	<ul style="list-style-type: none"> Surfaces include: tile, short carpet, concrete Obstacles include: walls, chair legs, cords, clothing
return_movement/sension_dsig	<ul style="list-style-type: none"> Function calls which demand motor movement in all 4 directions
motors_movement/sensing_dsig	<ul style="list-style-type: none"> PWM DC signal powering 2 motors PWM frequency of 1.6KHz. Draw of 0 - 0.45A Duty cycle of 0-40% 2 active high inputs; 5V high, 0V low

Testing Plan Overview - Movement Sensing / Motor Comm




5 Steps:

- A. Setup
- B. Forward movement test
- C. Left object test
- D. Right object test
- E. Front object test

Conclusion:

If the block passes all of the listed tests, all interface properties have been verified and the block is ready for inclusion into the system.

Schematic and Testing Setup - Movement Sensing / Motor Comm



Test Video - Movement Sensing / Motor Comm



Testing the object detection / avoidance

Test Results - Movement Sensing / Motor Comm

Results: All Passed

The robot accurately responded to all provided inputs. This demonstrates that the motor block is ready to be incorporated into the system for further testing and should not result in system damage or malfunctions.

Add'n Block Robot Housing

Interface	Properties
robot_outside_envin	<ul style="list-style-type: none"> Surfaces include: tile, short carpet, concrete Obstacles include: walls, chair legs, cords, clothing
station_robot_dcpwr	<ul style="list-style-type: none"> IMAX : 150mA 11.5-18V DC Conductive

